BUILDING B FLOOR PLAN

SCALE: 0' 4'

SHOP FLOOR
16' CLG. OPEN TO DECK
77'-10" X 55'-0"

BREAK ROOM
8' CLG.
14'-3" X 7'-3"

ADA RESTROOM
8' CLG.

ADA RESTROOM
8' CLG.

CABINET OFFICE 2
8' CLG.
9'-9" X 16'-1"

CABINET OFFICE 1
8' CLG.
9'-7" X 11'-1"

COMMERCIAL ICE MAKER

BAR TOP

WATER INLET

METAL CANOPY FOR DOOR # COMPRESSOR

5'-0" X 6'-0" PAD FOR COMPRESSOR 230V 30 AMPS

6'-0" X 6'-0" SLAB FLUSH WITH FINISHED FLOOR

6'-0" X 6'-0" SLAB FLUSH WITH FINISHED FLOOR

SWITCH RACK W/ INCOMING DATA FROM BUILDING A

SHOWERHEAD MOUNTED ON WALL WITH FULL TILED FLOOR. 4 WALLS TO 6' FLOOR TILE TO BE SLIP RESISTANT

DROP SLAB 3 1/2" IN THIS BATH ONLY FOR MUD BED FLOOR.

FIRE EXTINGUISHER

HAND RAIL SHALL BE COMPRISED OF WOOD OR STEEL; 42" GUARDRAIL AND 36" HANDRAIL W/ 1X HORIZONTAL RAIL AT CENTER TO MAINTAIN NO LARGER THEN 21" SPHERE FOR SAFETY

TOOL RACK

UP

WALL SHALL EXTEND TO DECK. THESE WALLS ONLY

3x14 STILE RACK

MITER SAW
12"-6" X 14'-0"
110V
15 AMPS

POCKET HOLE
2'-0"X3'-0"

5x14 STILE TABLE

DUST COLLECTOR
240V
20 AMPS

JOINER
120V
15 AMP

PLANNAR
230V
15 AMPS

TABLE SAW 2
230V
20 AMPS

TABLE SAW 1
230V
20 AMPS

FIRE EXTINGUISHER

BAND SAW
2'-0"X2'-0"

LINE BORE
2'-0"X3'-0"
110/220V
10.2 AMPS

EDGE SANDER
2'-0"X4'-0"
110/220V
20 AMPS

DUST COLLECTOR
120V
14 AMPS

HINGE BORE
2'-0"X3'-0"
110/220V
15 AMPS

FIRE EXTINGUISHER

DUST COLLECTOR
120V
14 AMPS

SHAPER
2'-0"X3'-0"
240V
1.2 AMP

FIRE EXTINGUISHER

4x8 LUMBER RACK

4x8 PLY. RACK

STANDARD METAL PANEL ALL AROUND WITH GUTTERS AT THE FULL PERIMETER

LANDING FLUSH WITH SIDEWALK/DRIVE SEE SITE PLAN

WALL & PARTITION LEGEND

PARTITION - WOOD STUD

EXTERIOR WALL