



CONTRACTOR TO VERIFY ADJACENT BUILDING FOOTING DURING EXCAVATION AND PROVIDE TEMP. SHORING IF NECESSARY. NOTIFY STRUCT. ENGINEER

- NEW CONSTRUCTION PLAN - GENERAL NOTES
- WHETHER INDICATED OR NOT, LIFE SAFETY SYSTEMS SUCH AS FIRE SPRINKLERS, FIRE ALARM SYSTEM, AND EMERGENCY LIGHTING SYSTEM SHALL BE ADJUSTED AS NECESSARY AND AS REQUIRED TO MEET CODES IN COORDINATION WITH THE ENTIRE BUILDING.
  - PATCH AND REPAIR ALL CONSTRUCTION IN THE AREAS OF DEMOLITION, AS NECESSARY TO ACCOMMODATE NEW CONSTRUCTION AND FINISHES. THIS INCLUDES PATCHING HOLES, FILLING DEPRESSIONS, LEVELING SURFACES, AND SIMILAR WORK AS NECESSARY TO MAKE REPAIRED SURFACES APPEAR AS NEW.
  - PERFORM ALL NEW CONSTRUCTION INDICATED, AND SUCH ADDITIONAL CONSTRUCTION AS NECESSARY TO ACCOMPLISH A COMPLETED PROJECT. COORDINATE NEW CONSTRUCTION WITH ARCHITECTURAL PLANS.
  - VERIFY LOCATION OF CLOSE-BY STRUCTURAL MEMBERS AND UTILITIES BEFORE TRENCHING OR CORING FOR NEW WORK.
  - NEW FLOOR FINISHES INDICATED ON PLANS SHOW APPROXIMATE EXTENT OF NEW CONSTRUCTION. GENERAL CONTRACTOR SHALL ADJUST THE EXTENT OF NEW CONSTRUCTION AS NECESSARY TO ACCOMMODATE ANY ADDITIONAL DEMOLITION, AND AS NECESSARY TO ACCOMPLISH BLENDING OF NEW AND EXISTING TILES.
  - NOTIFY ARCHITECT OF EXISTING CONCRETE-SLAB CONTROL JOINTS DISCOVERED DURING DEMOLITION THAT WILL UNDERLAY HARD FINISHES, SO THAT JOINTS IN THE FLOOR FINISH MAY BE RELOCATED AS NECESSARY. PROVIDE CRACK-ISOLATION MEMBRANE AS INDICATED, AS SPECIFIED, AND AS NECESSARY TO ACCOMMODATE NEW FLOOR FINISHES.
  - PROVIDE BACKING OR BLOCKING OF METAL OR OF FIRE-RETARDANT WOOD, AS NECESSARY FOR WALL-MOUNTED ITEMS.

**A1** 1ST FLOOR PLAN  
1/8"=1'-0"

TRUE NORTH  
PLAN NORTH