

Baton Rouge is the mirror image of this plan

- LEGEND**
- SANITARY SEWER LINE
 - VENT LINE
 - CONDENSATE DRAIN
 - FLOOR DRAIN
 - TRENCH DRAIN
 - HUB DRAIN
 - HOT WATER LINE - 110°
 - HOT WATER LINE - 140°
 - HOT WATER LINE - 180°
 - GAS LINE
 - HUB DRAIN
 - FLOOR DRAIN/SINK
 - TRENCH DRAIN
 - CLEANOUT
 - FLOOR/GRADE
 - WALL
-
- FS FLOOR SINK
 - FD FLOOR DRAIN
 - TD TRENCH DRAIN
 - HD HUB DRAIN
 - WC WATER CLOSET
 - UR URINAL
 - LAVATORY
 - WATER HEATER
 - TRAP PRIMER
 - HOSE BIBB
 - PLUMBING CONTRACTOR
 - GENERAL CONTRACTOR
 - OWNER/FRANCHISEE

DRAIN/VENT PLAN

SCALE: 3/16" = 1'-0"

PLUMBING CONTRACTOR SHALL REFER TO SHEETS F1 THROUGH F7 FOR INFORMATION PERTAINING TO REQUIREMENTS FOR RESTAURANT EQUIPMENT.

CONSTRUCTION NOTES:

- 1 THE PLUMBING CONTRACTOR SHALL PROVIDE AND INSTALL 10' MINIMUM OF CAST IRON WASTE SPRING LEADER.
- 2 INTERCONNECT SINK COMPARTMENT DRAINS WITH INDIRECT WASTE FEED STATE AND LOCAL CODE REQUIREMENTS.
- 3 6" ABS PLASTIC PIPE FOR STRAP LINES PROVIDE LONG SWEEP BEND THRU FLOOR EACH END WITH TOP 4" ABOVE FINISHED FLOOR.
- 4 SEE SHEET F3 FOR BOX OUT REQUIREMENTS BY MANUFACTURER TO FACILITATE FSI.
- 5 P.C. SHALL SUPPLY AND INSTALL CONDENSATE DRAIN LINE DOWN FROM DISHWASHER HOOD TO FLOOR SINK UNDER DISHWASHER. VERIFY SIZE WITH HOOD MANUFACTURER.
- 6 SEE SHEET P2 FOR TRAP PRIMER CONNECTION REQUIREMENTS.
- 7 P.C. SHALL ROUTE INDIRECT WASTE TO FLOOR SINK UNDER S.S. CHICKEN SINK, ITEM #33.
- 8 P.C. SHALL CONNECT 3/4" PVC, SCH. 40 DRAIN TO CHICKEN HEADER RACK, ITEM #71. PROVIDE PENETRATION IN COOLER WALL AND EXTEND 3/4" DRAIN TO FLOOR SINK UNDER S.S. CHICKEN SINK, ITEM #33. TERMINATE WITH 2" AIR GAP (MIN).
- 9 1 1/2" SCH. 40 PVC CONDENSATE DRAIN LINE INTERCONNECTED FROM RTU-2 AND RTU-3 DOWN TO HAND SINK (L2). SEE DETAILS 3/78 & 4/78.
- 10 1 1/2" SCH. 40 PVC CONDENSATE DRAIN LINE INTERCONNECTED FROM RTU-1 AND RTU-4 DOWN TO HAND SINK (L2). SEE DETAILS 3/78 & 4/78.
- 11 P.C. SHALL ROUTE CONDENSATE DRAIN FROM MEAT RAU. EVAPORATOR TO FLOOR SINK (F31) W/2" AIR GAP MIN.
- 12 5" DRINK PITCHON ABOVE CEILING FOR DRINK STATION AS AT BOTH SERVER STATIONS.
- 13 P.C. SHALL ROUTE CONDENSATE DRAINS FROM FREEZER/COOLER UNITS & EVAPORATOR TO HUB DRAIN WITH 2" AIR GAP MIN.
- 14 P.C. SHALL ATTEMPT TO LOCATE VENT WITHIN 14" OF ROOFLINE TO AS.

<p>golden corral</p>	<p>GO-11N.4.1 PROTOTYPE LEFT-HAND (MODIFIED)</p> <p>Location: BATON ROUGE, LOUISIANA Sherwood Forest Boulevard</p>	<p>SEAL</p> <p>MAUGHAN + RICHARD</p>	<p>Project</p>
-----------------------------	--------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------	----------------

Revision	THRU ADDENDUM	DATE
1	8/7/98	10/16/98
2	12/7/98	

DATE: 10/16/98

PLUMBING CONTRACTOR SHALL REFER TO SHEETS F1 THROUGH F7 FOR INFORMATION PERTAINING TO REQUIREMENTS FOR RESTAURANT EQUIPMENT.

SCALE: 3/16" = 1'-0"

DRAIN/VENT PLAN

CONSTRUCTION NOTES:

LEGEND

Baton Rouge is the mirror image of this plan